

- Notes:**
- A) All drops are 8" diameter to the machine. Then install a Y-Branch 6"/4"/4". Each machine has 2 4" diameter pick ups.
 - B) Main trunkline about 12 feet off of floor.
 - C) 8" Butterfly damper to each drop to adjust the air flow.

System 1

