

## System 2

**Notes:**  
A) All drops are 6" diameter to the machine. Then install a Y-Branch 6" 1/4". Each machine has 2 4" diameter pick ups.  
B) Main trunkline about 12 feet off of floor.  
C) 6" Butterfly damper to each drop to adjust the air flow.

