

**PO BOX 4686 ~AUSTINTOWN, OHIO 44515~PH:(330)-259-9009 FX:(330)-259-9001**

0.24

**NOTES: PLEASE REVIEW ALL DOCUMENTATION AT BOTTOM OF QUOTE**

Non standard crane equipment requirements may require field modification or adjustment in the field. Kundel Industries is not responsible any cost associate or adjustment in the field. Standard equipment is pre engineered components that are assembled and built the same way repetitively for different crane kits. Only Kundel Industries can qualify if a crane system is non standard.

**0**

NOTES:

Cust ID  
 Customer Avani Environmental  
 Address 95 Cypress Drive  
 Youngsville, NC 27596  
**bvenezia@avanienvironmental.com**

Contact: Bob Venezia  
 Phone: (919)570-2862  
 Fax: **(919)570-2863**  
 DATE: 8/12/2011  
 F.O.B.: Austintown, Ohio  
 Cell: (919)971-7261

Bridge Span is Based on O.D. of Floor Plates @ 23'

**SHIPPING REQUIREMENTS - LOADS MUST BE TARPED**

AND TRANSPORTATION MUST BE FLATBED

**SYSTEM LAYOUT**

Product: Bridge Capacity: **1000Lbs.**  
 Dimensions: **20' 7-3/8" X 19'** Hook Height (ft) **14**  
 Description: **480**

\$98.04 in proceeds from this order goes to a local non-profit rescue mission

**THE K-TRAC DESIGN**

- Capacities up to 6,000 lb
- Tuck in bridge and runway for minimum elevation loss
- Free standing posts with no cross brace
- Up to 45' hanging points~Ceiling and column hangers available
- Shortest endtruck in the industry for maximum work area
- Clean, low maintenance enclosed track
- Designed for easy installation and relocation
- Capacity changes possible on site
- Available with electrical components~Internal 60 amp electrical bar

**K-TRAC KITS**

- Complete custom kits to meet your needs ~Kits are certified
- Custom kit assembly drawings included with assembly directions

**K-TRAC SERVICE**

- Each system has a serial number for improved tracking and service
- Training and certification for installation,
- Electronically maintained inspection record

**APPROX WEIGHT**

2780 LB **Structural Subtotal \$5,136.07**

STRUCTURAL COMPONENTS		BASED ON WEIGHT OF KCI HOIST MODEL #	
XN050.50-16S1	LBS	60	1000 CAPACITY

**Electrical Components**

40	LF	Ebarinst	ELECTRIC BAR INSTALLED
2	Each	Collector	ELECTRICAL COLLECTOR
2	Each	Plug004	HOIST PLUG & BRIDGE PLUG

Electrical Subtotal \$1,399.60



**SPECIAL PAINT APPLICATIONS REQUIRE PAINT SWATCH**

**ANCHOR BOLTS NOT INCLUDED WITH FREE STANDING CRANES \$ CREDIT LIMIT**

**CREDIT TERMS: TBD by Kundel Accounting ALL ORDERS SHIPPED F.O.B AUSTINTOWN, OH**

**ENDORSE:**

**I have read and agree to Kundel's Terms and Conditions**

**DATE: PO#**

**CRANE SERVICE PROTOCOL**

**NO SERVICE, REPAIRS, PARTS OR BACK CHARGES TO KUNDEL ARE ACCEPTABLE UNLESS THE FOLLOWING PROTOCOL IS FOLLOWED**(1) Details of the occurrence must be documented, along with digital photo, or the like, signed dated and faxed to Kundel for review. (2) Kundel will inform of what is to be performed and time allocated to rectify the situation.(3) A requisition or work order will be given by Kundel BEFORE any work is performed by any company on the Crane System.

**ESTIMATED SHIP DATE\*/ \*\* FROM SIGNED DRAWINGS**

**K-TRAC 3-6 WEEKS\***

**T-TRAC 6-8 WEEKS\***

**ALL T-TRAC MOTORIZATION 8-10 WEEKS\***

ALLOW A LONGER LEAD TIMES FOR UNUSUAL REQUIREMENTS Refer to www.kundel.biz for Terms & Conditions

**NET PRICE \$6,535.67**

**U.S. currency**

**CEILING HUNG GUIDELINES**

IF REQUESTED, KUNDEL WILL PROVIDE LOADING REQUIREMENTS AT THE POINTS FOR CEILING MOUNT CRANE SYSTEMS. ALL SITE ENGINEERING INCLUDING BUILDING STRUCTURE LOADING PROVIDED BY OTHERS.

1.5% of every sale goes directly to a local non-profit rescue mission  
**\*Estimated ship date is when system will be on dock for transportation pick up. Kundel is not responsible for transportation delays and, or timely deliveries as a result of transportation companies. KUNDEL WILL NOT PAY FREIGHT ON INCOMPLETE OR INACCURATE SHIPMENTS**

\*\*Kundel shall not be liable for delay in or failure to make shipment of crane system due to causes beyond it's control such as strikes, fires, epidemics, act of God, war, riot, back orders from suppliers (i.e... Steel, etc.)

**Changes on systems prior to shipment: 10% of the structural subtotal along with added material costs will be charged if changes are not submitted within three days of Kundel receiving order. Charge due to system change after deadline (does not include added material cost).**

**\$513.61**